


Drops labeled IDF4-DXXX are a single drop from building 400 IDF and can be removed, or used as part of new cabling.

Wall mount equipment boxes (see pictures) in 401 and 402 are to be removed, as well as all cabling labeled as A-J. Cabled labeled A-J are routed into the wall mount box. A switch in the wall mount box provides uplink to the IDF.

All cabled labeled A-J shall be removed. If drops labeled IDF4-DXXX are not used in new cabling, then those drops and cable shall be removed as well.

	FY2020 E-Rate - Section 2 - Cabling.vsd 401/402 Existing Cabling		
	Latest Update: 3/18/2020		Created By: McNutt, James
Colorado River Schools 1004 Hancock Rd, Bullhead City, AZ Voice: 928-758-3961 Fax: 928-758-4996 www.crsk12.org	SCALE: Not To Scale	DATE: 3/18/2020	SHEET: 1 OF 2
	REV. CRSK12 Tech Contact		




All drops, cable, jacks, etc. shall be Cat6 or greater and shall originate from the IDF cabinet.

- △ X Cat 6 data drop where X = the number of drops
- △ 6 Cat 6 data drop in a service pole / power pole – 6 drops

* Please install a service pole that include at least 1 120v 20a outlet.
 District will be responsible for installing power, but we expect vendor to leave all all provided 120v accessories with IT Department or attached to pole.

13 Cabling locations with 58 data drops.

Vendor will need to provide at least one 48 port patch panel.
 District would prefer Keystone Jack style panels.
 Room 401 and 402 are approx. 30ftx30ft.

	FY2020 E-Rate - Section 2 - Cabling.vsd 401/402 New Cabling		
	Latest Update: 3/18/2020		Created By: McNutt, James
Colorado River Schools 1004 Hancock Rd, Bullhead City, AZ Voice: 928-758-3961 Fax: 928-758-4996 www.crsk12.org	SCALE: Not To Scale	DATE: 3/18/2020	SHEET: 2 OF 2
	REV. CRSK12 Tech Contact		